



## Licking County Library Parking Lot Improvements Bid Form

ITEM	DESCRIPTION	QUANTITY		Unit Cost	Extented Cost
		TOTAL	UNIT		
<b>BASE BID</b>					
201	CLEARING AND GRUBBING	1	LUMP		
202	PAVEMENT REMOVED (CONCRETE)	345	SQ YD		
202	PAVEMENT REMOVED (ASPHALT)	228	SQ YD		
202	CURB REMOVED	234	FOOT		
202	BUILDING FOUNDATION REMOVED	1	LUMP		
203	EXCAVATION	1	LUMP		
203	EMBANKMENT	1	LUMP		
204	SUBGRADE COMPACTION	3604	SQ YD		
253	PAVEMENT REPAIR, AS PER PLAN	38	SQ YD		
254	PAVEMENT PLANING	1538	SQ YD		
207	TACK COAT	733	GAL		
304	AGGREGATE BASE	573	CU YD		
448	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 2, PG 64-22	230	CU YD		
448	ASPHALT CONCRETE, SURFACE COURSE, TYPE 1, PG 64-22	420	CU YD		
448	ASPHALT CONCRETE, INTERMEDIATE COURSE, TYPE 1, PG 64-22 (SCRATCH COAT, AS DIRECT	20	CU YD		
451	NON-REINFORCED CONCRETE PAVEMENT	251	SQ YD		
608	4" CONCRETE WALK	1456	SQ FT		
609	CURB, STRAIGHT 18"	1833	FOOT		
SPECIAL	SNOW MELT SYSTEM	1	LUMP		
659	TOPSOIL	19	CU YD		
609	SEEDING AND MULCHING, CLASS 1	172	SQ YD		
630	SIGN ERECTED, FLAT SHEET	64	SQ FT		
630	GROUND MOUNTED SUPPORT, No. 2 POST	252	FOOT		
642	CROSSWALK LINE	60	FOOT		
642	TRANSVERSE/DIAGONAL LINE, TYPE 1	3070	FOOT		
642	HANDICAP SYMBOL MARKING, TYPE 1	10	EACH		
642	LANE ARROW	3	EACH		
642	PARKING STALL MARKINGS, TYPE 1	4510	FOOT		
603	6" ROOF DRAIN COLLECTOR (PVC, 707.45)	127	FOOT		
603	8" CONDUIT, TYPE B (PVC, 707.45)	95	FOOT		
603	12" CONDUIT, TYPE B (RCP, 706.02)	213	FOOT		
603	12" CONDUIT, TYPE B (CPP, 707.33)	406	FOOT		
603	12" CONDUIT, TYPE B (PVC, 707.45)	164	FOOT		
603	12" CONDUIT, TYPE C (CPP, 707.33)	100	FOOT		
604	MANHOLE (MH-1.1 "DOGHOUSE")	1	EACH		
604	CURB INLET (600-2)	1	EACH		
604	CATCH BASIN (CB No. 2-2B)	11	EACH		
SPECIAL	CLEANOUT	4	EACH		
SPECIAL	ROOF DRAIN DOWNSPOIUT RECONNECTION, AS PER PLAN	5	EACH		
805	3/4" WATER SERVICE TUBING	211	FOOT		
805	2" WATER SERVICE TUBING	170	FOOT		

ITEM	DESCRIPTION	QUANTITY		Unit Cost	Extented Cost
		TOTAL	UNIT		
805	GROUND MOUNTED SPIGOT BOX	2	EACH		
915	CLEANOUT	2	EACH		
918	6" SANITARY CONNECTION SERVICE PIPE	160	FOOT		
SPECIAL	SITE LIGHTING, COMPLETE	1	LUMP		
207	PERIMETER FILTER FABRIC FENCE	765	FOOT		
207	INLET PROTECTION	19	EACH		
SPECIAL	STABILIZED CONSTRUCTION ENTRANCE	1	EACH		
SPECIAL	CONCRETE WASHOUT	1	EACH		
614	MAINTAINING TRAFFIC	1	LUMP		
623	CONSTRUCTION LAYOUT STAKES	1	LUMP		
324	MOBILIZATION	1	LUMP		
				<b>BASE BID</b>	\$ -

ALTERNATE 1 - CONCRETE PATH					
ITEM	DESCRIPTION	TOTAL	UNIT		
608	4" CONCRETE WALK	1,837	SQ FT		
				<b>ALT. 1 TOTAL</b>	
				<b>BASE BID TOTAL + ALTERNATE 1</b>	